Form 10-300 (July 1969)

Z

UNITED STATES DEPARTMENT OF THE INTERIOR

NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES

INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

# Rhode Island

STATE

| COUNT | Y: |  |  |
|-------|----|--|--|
|       |    |  |  |

Washington

FOR NPS USE ONLY ENTRY NUMBER DATE

1. NAME \$4.000° COMMON Babcock-Smith House AND/OR HISTORIC: Babcock (Dr. Joshua) House; Smith (Orlando) House 2. LOCATION STREET AND NUMBER: 124 Granite Street CITY OR TOWN: Westerly STATE COUNTY: CODE CODE Rhode Island 02891 Washington 009 3. CLASSIFICATION CATEGORY **ACCESSIBLE** OWNERSHIP **STATUS** (Check One) TO THE PUBLIC District □ Public X Building Public Acquisition: Yes: Occupied Site ■ Restricted Structure 🔀 Private ☐ In Process Unoccupied Unrestricted ☐ Both Being Considered ☐ Object Preservation work X No in progress PRESENT USE (Check One or More as Appropriate) Agricultural ☐ Government ☐ Park ☐ Transportation ☐ Comments Commercial [ Industrial Trivate Residence Other (Specify) ■ Educational ☐ Military Religious ☐ Entertainment Museum 4 OWNER OF PROPERTY OWNER'S NAME: Phebe A. B. Smith, Trustee under the will of Orlando Smith STREET AND NUMBER: 124 Granite Street CITY OR TOWN: STATE: CODE Westerly Rhode Island 44 02891 5. LOCATION OF LEGAL DESCRIPTION COURTHOUSE, REGISTRY OF DEEDS, ETC: Town Clerk STREET AND NUMBER: Town Hall, 49 Broad Street CITY OR TOWN: CODE Westerly Rhode Island 02891 44 6. REPRESENTATION IN EXISTING SURVEYS TITLE OF SURVEY: ENTRY Historic American Buildings Survey DATE OF SURVEY: 1957 FOR NPS USE X Federal State County ☐ Local DEPOSITORY FOR SURVEY RECORDS: NUMBER Library of Congress STREET AND NUMBER: Independence Avenue and 1st Street, N.E. ONLY CODE Washington District of Columbia Ō 11

|   | ι | , |   |
|---|---|---|---|
|   | • | _ | • |
|   | F | 1 | 1 |
|   | ſ | I | 1 |
|   |   |   | • |
|   | - | _ | • |
|   | 2 |   |   |
|   |   | , |   |
|   |   |   |   |
| • |   | i | l |
| ; | , | Ù | J |
| ( | _ |   |   |
|   |   |   |   |
| 1 |   | 7 | ) |
|   | _ | + | I |
|   | _ | _ |   |
| ( | _ | 2 | , |
|   |   |   |   |
|   |   | _ |   |
| • | , | 1 |   |
|   |   |   |   |

| •   | DESCRIPTION |             |           |             | (Check One)  |       |                 | <u> </u> |
|-----|-------------|-------------|-----------|-------------|--------------|-------|-----------------|----------|
| i   | CONDITION   | ☐ Excellent | XX Good   | ☐ Fair      | Deteriorated | Ruins | Unexposed       |          |
|     | CONDITION   |             | (Check Or | 10)         |              | (Che  | ck One)         |          |
| Į   |             | □X Alte     | red       | ☐ Unaltered | ,            | Moved | 🔀 Original Site |          |
| - 1 | 25552112    |             |           |             |              |       |                 |          |

ESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

Dating from 1750 or before, the house built for Dr. Joshua Babcock on an elevated site in Westerly is a locally conspicuous, handsome and typical example of the dwelling of a comfortably prospering American colonial of the mid-XVIII Century. It is a timber-framed, clapboarded structure of two-and-one-half storeys upon a stone basement, with a large central chimney of stone, plastered over. It is covered by a gambrel roof of wood shingles which, on the east, is brought down over a rear extension, in "salt-box" profile. There is a one-and-one-half storey gabled ell (buildt c. 1848 to replace a less commodious XVIII-Century one) which extends to the north and whose front is a flush extension of the main house's entrance elevation; the ell has also a (tall and thin) central chimney. Cellar spaces extend under most of the main house and most of the ell; in the former, two large cellar chambers are connected by a brick arch through the large chimney base; in the latter there is also a partial sub-cellar, said to have been made for wine storage.

The main house has a five-bay front elevation and had, originally, two widely-spaced windows on each major floor, and one in the gable, at the ends. At the south end, two smaller windows have been introduced in irregular placement in the "salt-box" extension; at the northern end, the ell partially covers the original arrangement of openings. Thiss ell extends the north-south elevation by four bays. Front entrance to the main house is through an imposing doorway in its central bay (now forward from the surface of the house and fronting a small vestibule), and front entrance to the ell is a doorway in its third bay to the north. A low, gable-roofed vestibule (modern) projecting near the south-east corner of the house encloses a basement gangway which probably originally had a simple shed-type covering hatch.

Simple in exterior form and fenestration, the house is also simple in exterior trim, with certain emphatic, intended exceptions. Along the front of the house the gambrel roof extends well forward of the wall plane, and this generous eaves angle houses a pronounced and heavy projecting moulded cornice which has long, narrow modillions beneath it. Beneath the modillions a moulded architrave band runs across the facade and is brought forward to cap each of the second-floor windows, whose frames—like those below, and typical of early buildings—project well out from the clapboard wall surface. All windows have simple moulded sills; however, the first-floor windows have deep, high and heavy moulded capping cornices with (due to the projecting window frames) a noticeable end return against the house. This latter treatment has been followed on the front windows of the much later ell also, but side and rear windows around the house are not similarly elaborated. (Principal windows of the main house have 9-over-9 sashes, which are probably restorations.)

The main decorative feature of the house is its large front door-way: Surrounded by a robustly-moulded architrave, the six-panelled door

(See Continuation Sheet)

Form 10-300a (July 1969)

### UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

# NATIONAL REGISTER OF HISTORIC PLACES INVENTORY - NOMINATION FORM

(Continuation Sheet)

| STATE - Rhode Island |      |
|----------------------|------|
| COUNTY               |      |
| Washington           |      |
| FOR NPS USE ONL      | -Y   |
| ENTRY NUMBER         | DATE |
|                      |      |

(Number all entries)

### 7. Description.

(probably also a restoration) is flanked by fluted Tuscan pilasters upon panelled pedestals; these support a frieze, which breaks forward over them, and a wide and impressive broken-scroll pediment with carved rosettes in its volutes. The base cornice of the pediment is also brought forward over the pilasters, and again at its middle, where it supports a panelled plinth rising against the tympanum. At this central point the moulded architrave is given a curved pinch or point upwards, as if to form a bracket for the plinth above. This is the frontal pièce de résistance; the ell has its front doorway of simple Greek Revival design, and the other elevations are modest and silent.

Internally, the house has on its principal floors the expected, customary five-room plan dictated by a central chimney. An entry hall immediately behind the added front vestibule contains the main staircase, rising in three angular runs against the chimney and having a ramped rail supported by three varieties of twisted balusters rising from each tread and a twisted newel encaged in carved openwork (all now, if not originally, shown in natural wood finish). A ramped wainscot moulding echoes the line of the band-rail. The principal reception rooms open off the hall to north and south--the parlour to the south having a fully-panelled and pilastered fireplace wall, a wooden cornice, embrasured windows with interior shutters and window-seats, an elaborately pilastered and coved corner cupboard (all original). The dining-room to the north was lengthened towards the rear of the house in the restoration of the 1920's, and its fireplace wall then copied that of the parlour. The old kitchen across most of the rear of the house became a sitting-room after removal of domestic offices to the 1848 ell, but it retains its high and eight-foot-wide mortar-covered fireplace with oven; flanking the kitchen at the rear are small chambers. The plan of the second floor follows that of the first, but with simpler trim, although two upstairs chambers at the front of the house have panelled fireplace walls and hearth surrounds of old blue-and-white Dutch tiles.

The house remained in Babcock ownership until 1817. There was intervening ownership until 1818, when it was purchased by Orlando Smith, who was responsible for rebuilding of the ell. Successors in his family made alterations in the 1880's, which included the small hip-roofed vestibule which retains but protrudes the fine front doorway; a balcony added above; and stained-glass windows (now replaced) at the sides of the vestibule. Since the Smiths discovered, and prospered from, a nearby granite quarry, the residence property was early in their time given the granite walls and copings which still surround it on three sides. Later Smiths, in 1926-1928, engaged Norman Isham, a Providence architect and historian of local architecture, to restore the house to its original appearance as much as possible. This he did with characteristic expertise and sympathy, and-excepting the nevertheless harmonious later ell--the house is now presented as of the XVIII Century. Careful collecting and sorting by Smith occupants leave the house now with valuable furnishings of that period and of the early XIX Century.

| PERIOD (Check One or More as  | Appropriate)                | 4               |                   |
|-------------------------------|-----------------------------|-----------------|-------------------|
| Pre-Columbian                 | ☐ 16th Century              | X 18th Century  | 20th Century      |
| ☐ 15th Century                | ☐ 17th Century              | X 19th Century  |                   |
| SPECIFIC DATE(S) (Il Applicab | le and Known) c. 1750       | , c. 1848       |                   |
| REAS OF SIGNIFICANCE (Che     | ock One or More as Appropri | ate)            |                   |
| Abor iginal                   | 🏋 🔣 Education               | . K Political , | Urban Planning    |
| Prehistoric                   | Engineering                 | Religion/Phi-   | (Specity)         |
| Historic                      | ☐ Industry                  | losophy         | 1. Medicine       |
| Agriculture                   | ☐ Invention                 | X Science       | 2. Site of first  |
| X Architecture                | ☐ Landscape                 | Sculpture       | Westerly Post Of- |
| ☐ Art                         | Architecture                | Social/Human-   | fice, est. by     |
| Commerce                      | Literature                  | itarian         | Benjamin Franklir |
| Communications                | ☐ Military                  | Theater         |                   |
| Conservation                  | ☐ Music                     | Transportation  |                   |

#### STATEMENT OF SIGNIFICANCE

From its first building and occupancy by the Babcocks, and then for more than one hundred years in use by the Smith family, this house has had an important position in the town of Westerly--topographically, historically, politically and socially. Even now, with shopping plazas, super-markets and eating-places nudging it, the house on its slightly elevated plot--with its walls, lawn and one or two outbuildings--retains its importance, though its physical survival will depend upon both recognition of its history and value and legal and financial support of its fabric.


Dr. Joshua Babcock was born in Westerly in 1707 and attended Yale College, where, in 1724, he was the first student from Rhode Island to receive a degree. Later he studied medicine and surgery in this country and in England. Returning to Westerly to practice the skills he had learnt, he gave time also to other important interests and demands. He was amember of the Rhode Island legislature, served as this colony's Chief Justice, and was among the founders of what is now Brown University. This many-faceted personage became a friend of Benjamin Franklin and was often host to him in Westerly, where they indulged in fishing and colloquia. In return for hospitality, Franklin provided his host's house with some of his newly-invented lightening-rods. When an independent American government had been declared, Franklin saw that his friend was appointed postmaster for the Westerly area, and the original ell of Babcock's house became the post office.

The local importance of the house was revived when it and its land were acquired, 1846-1848, by Orlando Smith, who had uncovered granite quarries nearby, producing wealth for himself and, for Westerly, prosperity and industry for many years to come. About 1848 he moved his household into the old Babcock dwelling, and ever since then descendants in the Smith family have given the house good care.


Smith heirs have now undertaken arrangements to devise the house to the Westerly Historical Society, which is willing to accept the property and responsibility for its future maintenance—with contents—as a head-quarters and house museum. Westerly is a bustling modern town, but it is also one which embraces a long period of Rhode Island history and events, a long succession of architectural styles: the Babcock—Smith house is of prime importance in all of these.


| .,,,,, | Downing, Antoinette F.: Early 1937), pp. 124, 128, 134, 3 Smith, Franklin C.: Unpublishe Society, Westerly, Rhode Is U.S. Works Progress Administrat Island. A Guide (Bostor | 135, 1<br>ed pape<br>sland,<br>tion.     | .46<br>er<br>N | 5, 147, 173, 193, 1<br>r read before the W<br>May, 1959.<br>Federal Writers' Pr | 95, 202, 235,<br>esterly Histo<br>oject: <u>Rhode</u> | 237.<br>rical     |
|--------|--|--|----------------|---|---|-------------------|
|        |  |  | <del></del>    |   |   |                   |
| 10.    | GEOGRAPHICAL DATA  LATITUDE AND LONGITUDE COORDINATE  DEFINING A RECTANGLE LOCATING THE PROPI  |  | ol             | LATITUDE AND LONG<br>DEFINING THE CENTER  |   |                   |
| ].     |  |  | R              |   | N TEN ACRES   |                   |
| ļ      | CORNER LATITUDE LONGITUD   |  | -              | LATITUDE  | LONGITUDI   |                   |
|        | Degrees Minutes Seconds Degrees Minutes S  | econds                                   |                | Degrees Minutes Seconds   |   | Seconds<br>2.68 W |
| ļ      | NW   |  |                | 41 ° 22 16.37 ° N   | 71° 49 12   | W                 |
|        | NE   | _ 1                                      | ļ              |   |   |                   |
|        | SE   | _  |                |   |   |                   |
| į<br>T | APPROXIMATE ACREAGE OF NOMINATED PROPER  | ту: ар                                   | י.<br>נכוכ     | rox. one acre 4   | 34  |                   |
| ŀ      | LIST ALL STATES AND COUNTIES FOR PROPERTIE   | 5 OVERL                                  | L A            | PPING STATE OR COUNTY BO  | OUNDARIES   |                   |
|        |  | CODE                                     |                | OUNTY   | ,   | CODE              |
| - 1    | STATE:   |  | ┨              |   |   |                   |
| - 1    |  | CODE                                     | ١,             | COUNTY:   |   | CODE              |
| l      | STATE:   |  | ┨`             |   |   |                   |
| -      |  | CODE                                     | <del>  -</del> | OUNTY:  |   | CODE              |
|        | STATE:   | CODE                                     | ⇃`             | ÇON ( Y :   |   |                   |
|        |  |  | 1              |   |   | CODE              |
|        | STATE:   | CODE                                     | ۱٬             | COUNTY:   |   |                   |
|        |  |  | 1              |   |   |                   |
| 11     | FORM PREPARED BY   |  |                |   |   |                   |
|        | NAME AND TITLE:  |  |                |   | •   |                   |
|        | Richard B. Harrington, Consult   | ant                                      |                |   |   |                   |
| i      | Rhode Island Historical Preser   |  | n '            | Commission  | Dec. 24,  | 1971              |
|        | street and number:<br>52 Power Street  |  |                |   |   |                   |
|        | CITY OR TOWN:  |  | s              | TATE  |   | CODE,             |
|        | Providence   |  |                | Rhode Island 02   | 2906  | 44                |
| 130    | STATE LIAISON OFFICER CERTIFICATION  |  |                | NATIONAL REGIST   | ER VERIFICATION                                       | V                 |
| 44     | STATE ETAISON OF FICEN CENTING CASTON  | . (00***00000000000000000000000000000000 | 2112           | -   |   |                   |
|        |  |  | - 11           | •   | ž .   |                   |
|        | As the designated State Liaison Officer for the  | Na-                                      |                | I hereby certify that this p  | roperty is included                                   | in the            |
| •      | tional Historic Preservation Act of 1966 (Publi  | ic Law                                   | ļ,             | •   | roperty to increase                                   |                   |
|        | 89-665), I hereby nominate this property for inc   | clusion                                  | -              | National Register.  |   |                   |
|        | in the National Register and certify that it has   |  | 1              | ·   |   |                   |
|        | evaluated according to the criteria and procedu  | res set                                  |                | •   |   |                   |
|        | forth by the National Park Service. The recom  |  |                |   | tu and Winteria Pro-                                  |                   |
|        | level of significance of this nomination is:   |  | - 11           | Chief, Office of Archeolog  | gy and mistoric ries                                  | 861 1211011       |
|        | National X State Local   |  | ļ              |   | J   | i                 |
|        |  | لمما                                     | -              | •   | 4   |                   |
|        |  |  | $\parallel$    | Date  |   |                   |
|        | Name   |  |                |   |   |                   |
|        | 133  |  |                | ATTEST:   | -   |                   |
| 1      |  |  | ĺ              |   |   |                   |
|        | Title  |  |                |   | <u>-</u>  |                   |
|        |  | <del></del> ;                            |                |   | N Atomot D Atom                                       |                   |
|        |  |  |                | Keeper of The   | National Register                                     | ŀ                 |
|        |  |  |                | Tinte   |   |                   |
|        | Date   |  |                | Date  |   |                   |


9: MAJOR BIBLIOGRAPHICAL REFERENCES



CONDITIONS AFTER 1928







## NATIONAL PARK SERVICE

# NATIONAL REGISTER OF HISTORIC PLACES

### PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

| ГΑ | TE .  | The state of the s |    |
|----|-------|--|----|
|    | Rhode | Island   | ٠. |
|    |       |  |    |


Washington

|   | FOR NPS USE ON | LY   |
|---|----------------|------|
| 7 | ENTRY NUMBER   | DATE |

|     | COMMON: Babcock-Smith House   |     |
|-----|---|-----|
| 1 4 | AND/OR HISTORIC: Rabcock (Dr. Joshua) Smith (Orlando) House   |     |
| 2.  | LOCATION  |     |
|     | STREET AND NUMBER:  | 7 1 |
|     | CITY OR TOWN: Westerly  |     |
|     | Rhode Island CODE COUNTY:  Rhode Island Washington  | 009 |
| 3.  | PHOTO REFERENCE   | 12  |
|     | PHOTO CREDIT: Isaac G. Smith  |     |
|     | DATE OF PHOTO: 1971   |     |
|     | NEGATIVE FILED AT: Isaac G. Smith, 69 East Avenue, Westerly, Rhode Island   |     |
| 4.  | IDENTIFICATION  |     |
|     | Sketch-plans of cellar, first-floor and second-floor arrangements, and of south elevation, after restoration work by Norman Isham |     |

# BABCOCK - SMITH HOUSE

EARLY CONDITIONS AND CHANGES OF C. 1884



| UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE                      | Rhode Island                            |
|---|---|
| NATIONAL REGISTER OF HISTORIC PLACES  | Washington                              |
| PROPERTY PHOTOGRAPH FORM  | FOR NPS USE ONLY                        |
| (Type all entries - attach to or enclose with photograph)                           | ENTRY NUMBER DA                         |
| 1. NAME   |   |
| соммой: Babcock-Smith House   |   |
| AND/OR HISTORIC: Bahcock (Dr. Joshua) Smith (Orland                                 | o) House                                |
| 2. LOCATION   |   |
| 121 Granite Street  |   |
| CITY OR TOWN: Westerly  |   |
| Rhode Island CODE COUNTY:   | shington                                |
| 3. PHOTO REFERENCE  |   |
| KKODKKCREDIT: Isaac G. Smith  |   |
| рате об рното: 1971   |   |
| NEGATIVE FILED AT: Isaac G. Smith, 69 East Avenue, W.                               | esterly, Rhode Island                   |
| 4. IDENTIFICATION   | -                                       |
| DESCRIBE VIEW, DIRECTION, ETC.  |   |
| Sketch-plans of first- and second-floor a elevation, up to and including renovation | rrangements, and of south s of c. 1884. |

. . .



#### UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

## NATIONAL REGISTER OF HISTORIC PLACES

### PROPERTY PHOTOGRAPH FORM

| STATE          |      |
|----------------|------|
| Rhode Island   |      |
| COUNTY         |      |
| Washington     |      |
| FOR NPS USE ON | ILY  |
| ENTRY NUMBER   | DATE |
|                |      |

|  | MMON: Babcock-Smith House      | · · · · · · ·  | 111 /0 2 1 1 1                          |           |         |
|--|--------------------------------|----------------|---|-----------|---------|
|  | o/or Historic: Babcock (Dr. Jo | shua) House; S | mith (Orlando) Hous                     | se        |         |
| A4000000000000000000000000000000000000   | ATION                          |                | * |           |         |
| ST   | EET AND NUMBER:                |                |   |           |         |
|  | 124 Granite Street             |                |   |           |         |
| CIT  | Y OR TOWN:                     |                |   |           |         |
|  | Westerly                       |                |   |           |         |
| ST   | TE:                            | CODE           | COUNTY:                                 |           | СО      |
|  | Rhode Island                   | 44             | Washington                              |           | 00      |
| 3. PHO   | TO REFERENCE                   |                |   |           |         |
| РН   | TO CREDIT: Ross S. McElwee     |                |   |           | Months. |
| DA   | ге оf рното: November, 1971    |                |   |           |         |
| NE   | GATIVE FILED AT: Rhode Island  | Historical Pre | servation Commission                    | on, State | Hous    |
|  | 90 Smith Stre                  | et, Providence | . Rhode Island 0290                     | 03        |         |
| 4. IDE   | NTIFICATION                    |                | -                                       |           |         |
| B0000000000000000000000000000000000000   | SCRIBE VIEW, DIRECTION, ETC.   |                |   |           |         |
| B0000000000000000000000000000000000000   |                                |                |   |           |         |
| MARKET STATE OF THE STATE OF TH | Entrance (west) front.         |                |   |           |         |



# UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

# NATIONAL REGISTER OF HISTORIC PLACES

### PROPERTY PHOTOGRAPH FORM

| Rhode Island   |      |
|----------------|------|
| Washington     |      |
| FOR NPS USE ON | ILY  |
| ENTRY NUMBER   | DATE |
|                |      |

| 1. | NAME   |                    |             |  |  |  |
|----|--|--------------------|-------------|--|--|--|
|    | COMMON: Babcock-Smith House  | atemperate grania. |             |  |  |  |
|    | AND/OR HISTORIC: Rabcock (Dr. Joshua) House; Smith (Or                                       | lando) House       | - Tana - Ca |  |  |  |
| 2. | LOCATION   |                    |             |  |  |  |
|    | STREET AND NUMBER: 121 Granite Street  |                    |             |  |  |  |
|    | CITY OR TOWN: Westerly   |                    |             |  |  |  |
|    | Rhode Island code county:  | ington             | 009         |  |  |  |
| 3. | PHOTO REFERENCE  |                    |             |  |  |  |
|    | PHOTO CREDIT: ROSS S. McElwee  |                    |             |  |  |  |
|    | DATE OF PHOTO: November, 1971  |                    |             |  |  |  |
|    | NEGATIVE FILED AT: Rhode Island Historical Preservatio<br>90 Smith Street, Providence, Rhode |                    | House,      |  |  |  |
| 4. | IDENTIFICATION   |                    |             |  |  |  |
| 4. | DESCRIBE VIEW, DIRECTION, ETG.   |                    |             |  |  |  |



#### UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

### NATIONAL REGISTER OF HISTORIC PLACES PROPERTY PHOTOGRAPH FORM

| Υ .  |
|------|
| DATE |
|      |
| ֡    |

|   | COMMON: Babcock-Smith House AND/OR HISTORIC Babcock (Dr. Joshua) House; Smith (Orlando) House |            |         |  |                |      |
|---|---|------------|---------|--|----------------|------|
| 2. LO                                   |   | Silua) not | ر الله  | on (ortaino)   | House          |      |
| 200000000000000000000000000000000000000 | EET AND NUMBER:<br>121 Granite Street   |            |         |  |                |      |
| CIT                                     | y or town:<br>Westerly  | 1.0        | ****    |  |                |      |
| ST                                      | Rhode Island  |            | CODE C  | OUNTY:<br>Washingto  | on             | co   |
| 3. PHO                                  | TO REFERENCE  |            |         |  |                |      |
|   | TO CREDIT: ROSS S. McElwee  | 1          |         |  |                | •    |
|   | те огрното: November, 1971  |            |         |  | *** * 17/19 E  |      |
|   | ATIVE FILED AT: Rhode Island<br>90 Smith Stre   |            |         |  |                | Hous |
| 4. IDE                                  | 4. IDENTIFICATION   |            |         |  | <i>-</i>       |      |
| DE                                      | SCRIBE VIEW, DIRECTION, ETC.  | 1          | , to to |  |                |      |
|   |   |            |         | The same of the sa | t-box" extensi |      |



Form 10-301 (July 1969) UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

# NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY MAP FORM

(Type all entries - attach to or enclose with map)

| Rhode Island    |      |
|-----------------|------|
| COUNTY          |      |
| Washington      |      |
| FOR NPS USE ONL | Υ    |
| ENTRY NUMBER    | DATE |
| -               |      |

| 1. | NAME   |                   |
|----|--|-------------------|
|    | common: Babcock-Smith House  |                   |
|    | AND/OR HISTORIC: Babcock (Dr. Joshua) Smit   | n (Orlando) House |
| 2. | LOCATION   |                   |
|    | 124 Granite Street   |                   |
|    | Westerly   |                   |
|    | Rhode Island con   | CODE              |
| 3. | MAP REFERENCE  |                   |
|    | U. S. Geological Survey  |                   |
|    | SCALE: 1: 21,000   |                   |
| 2  | DATE: 1953   |                   |
| 4. | REQUIREMENTS   |                   |
|    | TO BE INCLUDED ON ALL MAPS  1. Property broundaries where required.  2. North arrow.  3. Latitude and longitude reference. |                   |